


# 24 INCH MANHOLE COVER AND FRAME



## NOTES:

1. VERIFY SLOTTED FRAMES ARE THOROUGHLY FILLED IN WITH MORTAR FOR EFFICIENT INTERACTION WITH IRON AND STRUCTURE.
2. VERIFY BEDDING MORTAR IS NOT IN CONTACT WITH EITHER HINGE HOUSING OR CUSHIONING INSERT.
3. VERIFY GASKET IS PROPERLY CLAMPED ON ITS FRAME GROOVE ALONG ITS ENTIRE LENGTH.
4. GASKET CAN BE REPLACED; USE ONLY ORIGINAL GASKET, AVAILABLE THROUGH AUTHORIZED DEALERS.
5. 24 INCH MANHOLE LID IS FITTED WITH AN INFILTRATION PLUG LOCATED IN THE HINGE HOUSING OF THE FRAME. VERIFY PLUG IS PROPERLY INSTALLED BEFORE INSTALLING THE FRAME.
6. REQUIRED ON ALL ARTERIALS, COLLECTORS OR ANY TIME THAT THE IRON WILL BE WITHIN THE TRAVEL LANE.
7. LID SHALL BE MARKED "SEWER", "STORM" OR "DRAINAGE".
8. CITY OF KIRKLAND LOGO REQUIRED.
9. LID MUST BE COVERED WITH TAR PAPER BEFORE OVERLAY.
10. PRODUCT SUPPLIED BY EAST JORDAN IRON WORKS, OR APPROVED EQUAL.

CITY OF KIRKLAND	
PLAN NO. CK-D.18A	
CITY OF KIRKLAND WASHINGTON	MODIFIED 24" MANHOLE FRAME W/ HINGED COVER